



Marten Falls Upgrade Project

The Marten Falls Upgrade Project is the largest construction project Remotes has ever undertaken!

This impressive upgrade has increased the amount of power available to Marten Falls First Nation by 50 per cent, allowing for the connection of more homes and community buildings. When it was completed in November 2021, it took 14,000 people hours to complete. The project includes a new one-megawatt (MW) generator, exhaust stack, radiators, transformers, and a new building.

New 1MW Generator Specifications:

- CAT model 3512C
- has 12 cylinders
- produces 1476 horsepower
- weighs 34,500 pounds
- capable of using 266 litres of diesel every hour at full load



This new generator will allow Marten Falls First Nation to connect many more buildings to the distribution system and provide reliable electricity for years to come.



